

Engineering Procedure
Electrical Distribution Unit

PR D 78106

Inspection and Testing of Fixed Electrical Equipment

Version 1.2

Date in Force: 19 February 2019

Approved by: Nadine Youssef
 Associate Director
 Electrical Distribution Unit
 Engineering System Integrity

Authorised by: Jonathon McKinnon
 Engineering Technical
 Publications Manager
 System Integrity Unit

Disclaimer

This document was prepared for use by persons in connection with works on or near the rail network electricity system operated by Sydney Trains. Sydney Trains makes no warranties, express or implied, that compliance with the contents of this document shall be sufficient to ensure safe systems or work or operation. It is the document user's sole responsibility to ensure that the copy of the document it is viewing is the current version of the document as in use by Sydney Trains. To the extent permitted by law, Sydney Trains excludes any and all liability for any loss or damage, however caused (including through negligence), which may be directly or indirectly suffered in connection with the use of this document.

Copyright

The information in this document is protected by copyright and no part of this document may be reproduced, altered, stored or transmitted by any person without the prior consent of Sydney Trains.

Document control

Version	Date	Author/ Prin. Eng.	Summary of change
1.0	28 April 2015	Chris Leung	First issue as a Sydney Trains document, rebranded from previous RailCorp SMS-06-EN-0557 V1.2
1.1	8 May 2018	Chris Leung	Three year review, no technical change
1.2	19 February 2019	Nick Loveday	Updated PR D 78106 "Approved by" to Associate Director Electrical Distribution Unit

Summary of changes from previous version

Summary of change	Section

Table of Contents

- 1 Purpose and scope4**
- 2 1500 Volt or High Voltage electrical equipment.....4**
 - 2.1 General.....4
 - 2.2 Tests where equipment under test is energised from the 1500 volt dc or HV system4
 - 2.3 Other tests where equipment under test is energised from the test equipment4
 - 2.4 Tests within substations requiring repeated isolation5
- 3 Low Voltage equipment.....5**
- 4 References5**

1 Purpose and scope

To provide the procedures for the in-situ inspection and testing of high voltage (HV), 1500V DC, and low voltage (LV) electrical equipment such as switchgear, cables, transformers, overhead lines and 1500V DC overhead wiring.

This procedure does not apply to:

- the testing of portable LV equipment, or
- testing carried out in a testing laboratory or similar facility.

2 1500 Volt or High Voltage electrical equipment

2.1 General

All aspects of testing work, including connection and disconnection of the equipment under test, the test equipment and the actual testing operations, shall be carried out in accordance with *PR D 78700 Working around Electrical Equipment*, except as set out in sections 2.2, 2.3 and 2.4 below.

2.2 Tests where equipment under test is energised from the 1500 volt dc or HV system

If an Electrical Permit to Work or a Substation Access Permit is required for the connection of the test equipment, the Permit shall be cancelled before the equipment under test is energised from the 1500 volt dc or HV system for the test. Alternatively, in the case of testing being carried out from within a substation, an Extraordinary Substation Access Permit may be used.

The use of a Test Electrical Permit to Work or a Test Substation Access Permit is not applicable for tests carried out when the equipment under test is energised directly from the 1500 volt dc or HV system. For example, when performing tests on equipment in the withdrawn state such as drop out tests on Direct Current Circuit Breakers (DCCB's).

2.3 Other tests where equipment under test is energised from the test equipment

When testing requires test equipment to be connected to HV equipment under test and earths are to be removed while the equipment under test is still isolated, the work shall be carried out under a Test Electrical Permit to Work or a Test Substation Access Permit.

When testing requires test equipment to be connected to 1500 volt dc equipment under test and rail connections are to be removed while the equipment under test is still isolated, the work shall be carried out under a Test Electrical Permit to Work (and a Test Substation Access Permit if appropriate). Refer to procedure *PR D 78500 Electrical Permits*.

If testing 1500 volt dc equipment within substations requires the use of test equipment that applies a voltage in excess of 50 volts ac or 120 volts dc to the equipment, the following requirements shall be complied with:

- an Authorised Person (Substations) competent of undertaking the required test shall either carry out the tests or shall check the details of the tests to be carried out and the isolation arrangements with the person carrying out the tests, and shall be present to ensure that the agreed arrangements are followed, and

- the person carrying out the tests shall have sufficient knowledge of the test procedures and is responsible for ensuring that the testing is carried out safely, and
- an Eligible Person (refer *PR D 78502 Substation Access Permit* or *PR D 78501 Electrical Permit to Work*) shall hold the required Electrical Permit(s) for the 1500 volt dc equipment being tested, and
- all persons involved in the testing shall be signed onto the Electrical Permit(s), and
- all persons in the vicinity shall be warned to keep clear (see Note below) prior to the test voltage being applied.



Note:

The minimum Safe Approach Distances (SAD) from the equipment to be tested must not be infringed. The SAD depends on the test voltage that will be applied during the test. SAD's are documented in System Guide *PR D 78700 Working around Electrical Equipment* Table 1.

2.4 Tests within substations requiring repeated isolation

When testing, inspection or adjustment of 1500 volt dc or high voltage equipment within substations requires repeated isolation and restoration of supply, the work may be carried out under a single Extraordinary Substation Access Permit instead of a number of Substation Access Permits. Refer *PR D 78502 Substation Access Permit* Section 11 Extraordinary Substation Access Permit for details.

3 Low Voltage equipment

When carrying out testing using test equipment that applies a voltage in excess of 50 volts ac or 120 volts dc to the Low Voltage equipment under test, the following precautions shall be observed:

- there shall be no Low Voltage Access Permits in force for the equipment unless they are held by the person carrying out the tests, and
- the equipment shall be isolated and proved dead prior to connecting the test equipment, and
- all persons in the vicinity shall be warned to keep clear (see Note above) prior to the test voltage being applied.

4 References

PR D 78700 Working around Electrical Equipment

PR D 78500 Electrical Permits

PR D 78502 Substation Access Permit

PR D 78501 Electrical Permit to Work